



LANGSTONE HARBOUR
LOCAL NOTICE TO MARINERS NO. 02 OF 2023

North Portsea Island Flood and Coastal Erosion Risk Management
Scheme: Phase 4b – Eastern Road

Mariners are advised that flood and coastal erosion risk management works will continue to take place on the foreshore between Salterns Lake and Kendall's Wharf. The Scheme will be constructed over a three-year period, with a Local Notice to Mariners issued at the start of each construction year. This LNTM relates to the works planned for 2023.

The works this year will consist of:

- The installation of a silt barrier along various sections of the works
- Piling and constructing of a new concrete floodwall
- Excavation along the toe of the existing wall to install piles which will form the shutter for the concrete base - between chainage 1675m and 2125m an additional pile approximately 3m further out
- Concrete casting of the new lower wall followed by the upper wall
- Between chainage 675m and 2125m, a stepped revetment and upper wall only
- Reinstatement of the excavated material back against the piles with the remainder spread over an area 10m from the wall
- Building a Roost Island for birdlife (details to be approved prior to commencement via planning and ML conditions)
- Finishing of concrete works to 2nr stairs

The only excavators on the foreshore at low water will be 8t excavators.

All works will be fully compliant with Marine License: L/2020/00098/1 and Planning consent: 19/01368/FUL. Further information can be obtained by [contacting the Coastal Partners Team](#).

Cancel Local Notice 04/2022.

Owners, Agents, Charterers, Marinas, Yacht Clubs and Recreational Sailing Organisations should ensure that the contents of this Notice are made known to the Masters or persons in charge of their vessels or craft.

Ferry Road
Hayling Island
Hampshire
PO11 0DG

B Johnson
Harbour Manager

9th February 2023