



**LANGSTONE HARBOUR**  
**LOCAL NOTICE TO MARINERS NO. 05 OF 2024**

**North Portsea Island Flood and Coastal Erosion Risk Management**  
**Scheme: Phase 4b – Eastern Road**

**Mariners are advised** that flood and coastal erosion risk management works will continue to take place on the foreshore between Salterns Lake and Kendall's Wharf. It is anticipated that the project will be completed this year and this LNtM relates to works planned for 2024.

The works this year will consist of:

- The installation of a portadam/silt curtain along the length of this phase approximately 17m out from the wall
- Piling and construction of a new concrete floodwall
- Excavation along the toe of the existing sea wall to install the piles which will form the shutter for the concrete base.
- Concrete casting of the new lower sea wall followed by the upper wall.
- Reinstatement of the excavated material back against the piles with the remainder spread over an area 10m from the wall on the foreshore.
- Removal of existing embankment flood defence (approx. 100m) in front of Langstone harbour carpark, once the new inland defence has been constructed. This will re-align the flood defence in this location.
- Completion of 2no new RC access steps

The only excavators on the foreshore at low water will be 8t excavators.

All works will be fully compliant with Marine License: L/2020/00098/1 and Planning consent: 19/01368/FUL. Further information can be obtained by [contacting the Coastal Partners Team](#).

Cancel Local Notice 02/2023.

**Owners, Agents, Charterers, Marinas, Yacht Clubs and Recreational Sailing Organisations should ensure that the contents of this Notice are made known to the Masters or persons in charge of their vessels or craft.**

B Johnson  
Harbour Manager

Ferry Road  
Hayling Island  
Hampshire  
PO11 0DG

30<sup>th</sup> May 2024